

Tender No: Biafo/Civil Work/ CW-01

Bill of Quantity Anfo Building Approach Road and Renovation of Anfo Magazine Civil Work					
S.No.	SCOPE OF WORK	Unit	Qty	Unit Rate	Total Amount
1	Excavation Work/ Shaving of Mound Area	CFT	2500		
	Excavation and Shaving of Mound Area in slope complete with all respect as approved and directed by Engineer Incharge				
2	Stone Dust	CFT	1350		
	Leveling compacting and laying stone dust with water curing and using the compactor machine as per our requirements complete with all respect as approved and directed by Engineer Incharge				
3	Leveling compacting	SFT	2500		
	Leveling compacting and dressing work complete with all respect as approved and directed by Engineer Incharge				
4	Tuff Paver	SFT	2600		
	Providing and laying 80 mm 7000 PSI Tuff Paver on approach road using sand csion as per requirement complete with all respect as approved and directed by Engineer Incharge				
5	Desimentling The Concrete Road	SFT	360		
	Desimentling the old approch road concrete complete with all respect as approved and directed by Engineer Incharge				
6	Kerb Stone	RFT	200		
	cast in situ concrete 1:2:4 kerb stone complete with all respect as approved and directed by Engineer Incharge				
7	Fance Gate	RFT	15		
	Fance Gate at the start of Anfo Building approach road complete with all respect as approved and directed by Engineer Incharge				
8	Drain Excavation Work	CFT	100		
9	P.C.C Concrete For Drain (1:2:4)	CFT	25		
	Provide and laying of PCC 1:2:4 cement concrete using graded screened bajri 3/4" (19mm) and down gauge in Beam with or without panels including ,consolidation, finising and curing etc complete with all respect as approved and directed by Engineer Incharge				
10	Anfo Magazine Renovation	LUMPSUM	—		
	Wall Repairs: Fix cracks and damages to walls to ensure structural integrity and safety. 2. Floor Maintenance: Clean, repair with 1:2:4 concrete, and refinish floors to prevent tripping hazards and improve appearance. 3. Roof Repairs: Inspect and repair roof leaks, damages, or weaknesses to prevent water ingress. 4. Staircase Repairs: Fix damaged or loose stairs, and other safety features. 5. Outer Area: Clean, repair, and landscape outer areas to make them usable and safe.				
Total Amount					

Bill of Quantity
Additional Tuff Pavers Work
Civil Work

S.No.	SCOPE OF WORK	Unit	Qty	Unit Rate	Total Amount
1	Stone Dust	CFT	3000		
	Leveling compacting and laying stone dust with water curing and using the compactor machine as per our requirements				
2	Tuff Paver	SFT	5000		
	Providing and laying 80 mm 7000 PSI Tuff Paver on approach road using sand csion as per requirement				
3	Kerb Stone	RFT	200		
	cast in situ concrete 1:2:4 kerb stone				
4	Drain ExcavationWork	CFT	100		
	Side Drain Excavation Work				
5	P.C.C Concrete For Drain (1:2:4)	CFT	150		
	Provide and laying of PCC 1:2:4 cement concrete using graded screened bajri 3/4" (19mm) and down gauge in Beam with or without panels including ,consolidation, finising and curing etc.				
6	P.C.C Concrete 1:2:4 For Edge of Tuff Paver	CFT	100		
	Provide and laying of PCC 1:2:4 cement concrete using graded screened bajri 3/4" (19mm) and down gauge in Beam with or without panels including ,consolidation, finising and curing etc.				
7	Mound Shaving and Cutting	CFT	800		
	As per requirement for mound shaving and cutting for havey traffic turning point				
Total Amount					